BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

APPROVED TENDER SCHEDULE –'B'

Name of Work:-Site preparation for indira canteen in Raithara santhe of ward no - 01 in Yelahanka sub division

Sl	Description	Unit	Approved Qty	Approved Rate KRIDL	
				Rate	Rate in Words
1	Removing B.S. slab of Drain and stacking.(P No.25 / I N 5.32)	Sqm	36.00	65.72	Rupees Sixty Five and Paise Seventy Two Only
2	KSRB 2-1.1 : Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications. specification. No. KBS 2.1 (a) / 2.3.1 (P.5/I.2.1)	Cum	237.60	166.42	Rupees One Hundred Sixty Six and Paise Forty Two Only
3	KSRRB M200-24:- dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces no exceeding 0.02 Cum in volume and stock piling at designated locations and disposal of dismantled materials upto a lead of 1000 meters, stacking serviceable and unserviceable materials separately complete as per specifications. MORTH specifications. No. 202, (P.No. 138/ Item No. 18.47)	Cum	5.40	827.86	Rupees Eight Hundred Twenty Seven and Paise Eighty Six Only
4	KSRRB M100-1 Loading and Unloading of Stone Boulder / Stone aggregate /sand/kaner/ Moorum KSRRB M100-1 Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications MORTH -100/ Chapter 1 (Page No.133/ Item No 17.1)	Cum	243.00	100.00	Rupees One Hundred Only
5	KSRB 2-2.1 : Earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications, specification, No, KBS 2.1(a) / 2.3.5, No.5/Item No. 2.3)	Cum	45.00	200.34	Rupees Two Hundred and Paise Thirty Four Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 016

	Description	Unit	Approved Qty	Approved Rate KRIDL	
				Rate	Rate in Words
6	Providing and fixing to wall, ceiling and floor, medium density polyethylene pipes 6.00 kgs/sq.cm working pressure 63mm outside diameter with special flange, compression type fittings, wall clips , making good the wall, ceiling and floor including cost all material, labour charges, HOM of equipments and testing complete as per specifications.(P.N .93 I.N 13.70.2)	Rmtr	50.00	289.38	Rupees Two Hundred Eighty Nine and Paise Thirty Eight Only
7	Providing and fixing to wall , ceilling and floor unplasticised PVC pipes 6.00 kgs/sq.cm working pressure with pipe fitting wall clips, making good the wall, ceilling and floor for sanitary pipelines including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications.-do- with 150mm dia (Page No.88/Item No. 12.116.4)	Mtr	20.00	879.80	Rupees Eight Hundred Seventy Nine and Paise Eighty Only
8	Refilling available earth around pipelines, cables in layers not exceeding 20cms in depth compacting each deposited layers by ramming after watering lead upto 50m and lift upto 1.5m including cost of labour complete as per specification (P.No.6 I.No.2.11)	Cum	45.00	80.56	Rupees Eighty and Paise Fifty Six Only
9	KSRB 13-6.3.1: Providing and fixing in position brass gate valve with C.I. wheel of approved quality (screwed end) 50 mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No. KBS 13.2.6 / 13.3 (Page No.92/Item No.13.37)	Each	1.00	2175.12	Rupees Two Thousand One Hundred Seventy Five and Paise Twelve Only
10	Providing and fixing on position brass bib cock of approved quality 25mm dia nomial bore including cost of all materials labour and HOM of equipments with all leads complete as per specifications.(P.N.91 I.N 13.25)	Each	2.00	288.32	Rupees Two Hundred Eighty Eight and Paise Thirty Two Only
11	Refixing stone slabs of drains and pointing in C.M.(1:3)(P.No.25/I.No.5.33)	Sqm	36.00	80.56	Rupees Eighty and Paise Fifty Six Only
12	1023 - Hire charges of Tractor 40HP including operator and fuel (P.No XXXXVI Code No.1023 Sl.No.19 PWD SR 2016-17)	Day	2.00	1520.00	Rupees One Thousand Five Hundred Twenty Only
13	1031 - Hire charges of J.C.B Excavator (P.No XXXXVI Code No.1031 Sl.No.23 PWD SR 2016-17)	Day	2.00	6720.00	Rupees Six Thousand Seven Hundred Twenty Only
14	Engaging Casual Labours (Unskilled mazdoor Heavy) (P.No.LIV Sl.No.5 PWD SR 2016-17)	Nos	20.00	258.88	Rupees Two Hundred Fifty Eight and Paise Eighty Eight Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

	Description	Unit	Approved Qty	Approved Rate KRIDL	
				Rate	Rate in Words
15	KSRRB M400-6.1. Construction of granular sub-base by providing close graded material, mixing in a mechaical mix plant at OMC, carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications. A. Plant Mix Method.Close graded granular sub-base material as per 400-1 For Grading- II Material (P.No.155 It.No.20.4.2)	Cum	33.60	1665.26	Rupees One Thousand Six Hundred Sixty Five and Paise Twenty Six Only
16	KSRB 4-1.3: Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.Specification No.KBS 4.1, 4.2 (P.12/I.4.3)	Cum	33.60	5159.02	Rupees Five Thousand One Hundred Fifty Nine and Paise Two Only
17	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC) M20 for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, for raft foundation, column footing, main and secondary beams with all lead and lifts etc.,complete (exclusive of cost of steel and fabrication charges.) Page No.18 / Item No. 4.48)	Cum	28.00	6231.74	Rupees Six Thousand Two Hundred Thirty One and Paise Seventy Four Only
18	Vaccum De-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator HOM of machinery Screed Vibratiry, Power Floater, blade and disc etc., with all lead and lift (P.177/ I.22.7)	Sqm	224.00	95.40	Rupees Ninety Five and Paise Forty Only
19	Providing Groove cutting for width of 5mm to 10mm and depth 80mm-100mm including cost of cutting machine generator and HOM of machinery including cost of blade, coolant etc., including cleaning aof groove & providing sand and hot bitumen fillars and filler metal etc.,including cost of conveyance of all materials, labour,lead and lift charges and all the other incidental charges as per drawing and as per specifications, MORTH specification. (P.178/ I.22.8)	Mtr	52.00	121.90	Rupees One Hundred Twenty One and Paise Ninety Only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.